REI LAB **Reservoirs Environmental, Inc.**

March 14, 2014

Subcontract Number:	**NA**
Laboratory Report:	**RES 284137-1**
Project # / P.O. #	**None Given**
Project Description:	**2605 Robin Dr**

Shannon Anderson
Anderson Property Inspections
115 Del Oro Circle
Colorado Springs CO 80919

Dear Customer,

Reservoirs Environmental, Inc. is an analytical laboratory accredited for the analysis of Industrial Hygiene and Environmental matrices by the National Voluntary Laboratory Accreditation Program (NVLAP), Lab Code 101896-0 for Transmission Electron Microscopy (TEM) and Polarized Light Microscopy (PLM) analysis and the American Industrial Hygiene Association (AIHA), Lab ID 101533 - Accreditation Certificate #480 for Phase Contrast Microscopy (PCM) analysis. This laboratory is currently proficient in both Proficiency Testing and PAT programs respectively.

Reservoirs Environmental, Inc. has analyzed the following samples for asbestos content as per your request. The analysis has been completed in general accordance with the appropriate methodology as stated in the attached analysis table. The results have been submitted to your office.

RES 284137-1 is the job number assigned to this study. This report is considered highly confidential and the sole property of the customer. Reservoirs Environmental, Inc. will not discuss any part of this study with personnel other than those of the client. The results described in this report only apply to the samples analyzed. This report must not be used to claim endorsement of products or analytical results by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without written approval from Reservoirs Environmental, Inc. Samples will be disposed of after sixty days unless longer storage is requested. If you have any questions about this report, please feel free to call 303-964-1986.

Sincerely,

Nicole Mari for

Jeanne Spencer
President

RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0

TDH Licensed Laboratory # 30-0136

TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: **RES 284137-1**
Client: **Anderson Property Inspections**
Client Project Number / P.O. **None Given**
Client Project Description: **2605 Robin Dr**
Date Samples Received: **March 7, 2014**
Method: **EPA 600/R-93/116 - Short, Bulk**
Turnaround: **3-5 Day**
Date Analyzed: **March 13, 2014**

ND=None Detected
TR=Trace, <1% Visual Estimate
Trem-Act=Tremolite-Actinolite

Client Sample Number	Lab ID Number	LAYER	Physical Description	Sub Part (%)	Asbestos Content: Mineral	Asbestos Content: Visual Estimate (%)	Non Asbestos Fibrous Components (%)	Non-Fibrous Components (%)
A26051	EM 1131838	A	Off white compound	5	**Chrysotile**	**4**	0	96
		B	Light blue/multi-layered paint	35		**ND**	0	100
		C	White/tan drywall w/ yellow/multi-layered paint	60		**ND**	45	55
A26052	EM 1131839	A	Off white compound	2	**Chrysotile**	**5**	0	95
		B	Light blue/multi-layered paint	8		**ND**	0	100
		C	White/tan drywall	90		**ND**	10	90
A26053	EM 1131840	A	White compound w/ pink & blue paint	3	**Chrysotile**	**2**	0	98
		B	White compound	12	**Chrysotile**	**5**	0	95
		C	Light blue/multi-layered paint	20		**ND**	0	100
		D	White/tan drywall	65		**ND**	45	55
B26051	EM 1131841	A	Light pink/multi-layered paint w/ white compound	1	**Chrysotile**	**TR**	0	100
		B	White compound	1	**Chrysotile**	**4**	0	96
		C	White/multi-layered paint	1		**ND**	0	100
		D	Tan mastic	1		**ND**	0	100
		E	White resinous caulk	11		**ND**	0	100
		F	White/dark brown fiberboard counter top	85		**ND**	65	35

RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0

TDH Licensed Laboratory # 30-0136

TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: **RES 284137-1**
Client: **Anderson Property Inspections**
Client Project Number / P.O. **None Given**
Client Project Description: **2605 Robin Dr**
Date Samples Received: **March 7, 2014**
Method: **EPA 600/R-93/116 - Short, Bulk**
Turnaround: **3-5 Day**
Date Analyzed: **March 13, 2014**

ND=None Detected
TR=Trace, <1% Visual Estimate
Trem-Act=Tremolite-Actinolite

Client Sample Number	Lab ID Number	LAYER	Physical Description	Sub Part (%)	Asbestos Content: Mineral	Asbestos Content: Visual Estimate (%)	Non Asbestos Fibrous Components (%)	Non-Fibrous Components (%)
C26051	EM 1131842	A	White resinous material	100		**ND**	0	100
D26051	EM 1131843	A	Off white compound	1	**Chrysotile**	**4**	0	96
		B	Dark brown mastic	2		**ND**	0	100
		C	White/blue paint w/ white compound	2		**ND**	0	100
		D	Pink/multi-layered paint	3		**ND**	0	100
		E	Off white mastic	4		**ND**	0	100
		F	White cove base	88		**ND**	0	100
E26051	EM 1131844	A	Colorless mastic	2		**ND**	0	100
		B	Light gray tile	98		**ND**	0	100

RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0

TDH Licensed Laboratory # 30-0136

TABLE PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: **RES 284137-1**
Client: **Anderson Property Inspections**
Client Project Number / P.O. **None Given**
Client Project Description: **2605 Robin Dr**
Date Samples Received: **March 7, 2014**
Method: **EPA 600/R-93/116 - Short, Bulk**
Turnaround: **3-5 Day**
Date Analyzed: **March 13, 2014**

ND=None Detected
TR=Trace, <1% Visual Estimate
Trem-Act=Tremolite-Actinolite

Client Sample Number	Lab ID Number	LAYER	Physical Description	Sub Part (%)	Asbestos Content: Mineral	Asbestos Content: Visual Estimate (%)	Non Asbestos Fibrous Components (%)	Non-Fibrous Components (%)
F26051	EM 1131845	A	Tan mastic	5		**ND**	2	98
		B	Off white sheet vinyl w/ gray fibrous backing material	95		**ND**	15	85

TEM Analysis recommended for organically bound material (i.e. floor tile) if PLM results are <1%.

Analyzed by: Michael Scales

Data QA: Nicole Mari

Due Date: ~~Standard Processing~~ 3.12 - 3.14

Due Time: ~~A.S.A.P.~~ 10:20

REI LAB Reservoirs Environmental, Inc.

RES 284137

SUBMITTED BY:		INVOICE TO: (IF DIFFERENT)		CONTACT INFORMATION:	
Company:	Anderson Property Inspections (A.P.I.)	Company:		Contact: Shannon Anderson	Contact: Ted Anderson
Address:	115 Del Oro Circle	Address:		Phone: 719-640-8489	Phone: 719-640-8489
	Colorado Springs, CO 80919			Fax: 206-203-0576	Fax:
				Cell/pager: 719-640-8489	Cell/pager: 719-640-3348
Project Number and/or P.O. #:				Final Data Deliverable Email Address:	
Project Description/Location:	2605 ROBIN DR.			shannonhurst@msn.com	

ASBESTOS LABORATORY HOURS: Weekdays: 7am - 7pm

PLM / PCM / TEM ☒ RUSH (Same Day) ___ PRIORITY (Next Day) ☒ STANDARD please

(Rush PCM = 2hr, TEM = 6hr.)

CHEMISTRY LABORATORY HOURS: Weekdays: 8am - 5pm

Metal(s) / Dust ___ RUSH ___ 24 hr. ___ 3-5 Day

RCRA 8 / Metals & Welding Fume Scan / TCLP ___ RUSH ___ 5 day ___ 10 day

Organics ___ 24 hr. ___ 3 day ___ 5 Day

Prior notification is required for RUSH turnarounds.

Analysis turnarounds are subject to laboratory sample volume and are not guaranteed. You will be notifited if delays are expected. Additional fees apply for afterhours and holidays for all analysis types.

Special Instructions: ____ Please stop @ positive and call w/results

REQUESTED ANALYSIS

VALID MATRIX CODES

Air = A | Bulk = B
Dust = D | Paint = P
Soil = S | Wipe = W
Drinking Water = DW
Waste Water = WW
Other = O
ASTM E1792 approved wipe media only

LAB NOTES:

	Client sample ID number (Sample ID's must be unique)	PLM - Short report, Long report, Point Count	TEM - AHERA, Level II, 7402, ISO, +/-, Quant, Semi-quant, Micro-vac, ISO-Indirect Preps	PCM - 7400A, 7400B, OSHA	DUST - Total, Respirable	METALS - Analyte(s) ___ RCRA 8, TCLP, Welding Fume, Metals Scan	ORGANICS - BTEX, MTBE, 8260, GRO, DRO	OTHER -	Sample Volume (L) / Area	Matrix Code	# Containers	Date Collected mm/dd/yy	Time Collected hh/mm a/p	EM Number (Laboratory Use Only)
1	A26051	✓								✓		3/6/14	1000A	1131838
2	A26052													9
3	A26053													40
4	B26051													1
5	C26051													2
6	D26051													3
7	E26051	✓												4
8	F26051	X								✓		✓	1120a	5
9														
10														
11														
12														
13														

Number of samples received: 8 (Additional samples shall be listed on attached long form.)

NOTE: REI will analyze incoming samples based upon information received and will not be responsible for errors or omissions in calculations resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested analysis as indicated on this Chain of Custody shall constitute an analytical services agreement with payment terms of NET 30 days, failure to comply with payment terms may result in a 1.5% monthly interest surcharge.

Relinquished By: Date/Time:

Laboratory Use Only

Received By: Elisa Meri Date/Time: 3.7.14 10:20 Carrier: Fedex

Sample Condition: On Ice Y/N Sealed Y/N Intact Y/N

Temp. (F°) ____

Results:	Contact	Page	Phone	Email	Fax	Date	Time	Initials	Contact	Page	Phone	Email	Fax	Date	Time	Initials
	Contact	Page	Phone	Email	Fax	Date	Time	Initials	Contact	Page	Phone	Email	Fax	Date	Time	Initials